HASSAN DIVISION.

Advertisement, dated 15th March 1895.

Tenders are hereby invited for constructing Deputy Amildar's Cutcherry at Alur, Hassan District.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. to 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor, and forwarded in sealed covers to the Executive Engineer before the 1st April 1895. The work should be completed by the end of June 1896.

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities of items of work required is given below. These quantities are not guaranteed.

Items of work.	*Per.*	*Quantity.*
Excavation	C. Yds.	180
Burnt brick in chunam	C. Ft.	15,636
Ditto arch works	Do	145
Plastering in chunam	Sqr.	128·80
Burnt stone slabs	Sqr. Ft.	72
Cornice work to pillars	R. Ft.	48
White and color washing	Sqr.	128·80
Quoins with mortor	Sqr. Ft.	84
Teak wood work wrought and put up	C. Ft.	267
Roofing with Mangalore flat tiles and teak reepers	Sqr.	39·18
Ridging with Mangalore ridge tiles	R. Ft.	138
Ventilating tiles	Each.	70
Flooring with concrete 6" thick	C. Ft.	1,012
Teak wood ornamental eave board	R. Ft.	364
Wooden brackets fixing, &c., complete	Each.	30
Matting with outer rend of bamboo	Sqr.	17·25
Teak wood door with pannelled shutters 1½" thick	Sqr. Ft.	258
Ditto battened ditto	Do	114
Ditto windows with glazed shutters, &c., with iron bars	Do	140
Ditto ditto ditto	Do	97
Circular windows with glazed shutters 2½" dia	Each.	2
Wood oiling	Sqr.	24·00
Painting to doors and windows	Do	20·00
Ceiling to lock-ups	Sq. Ft.	547
Planking 1" thick	Do	74
Wooden finials and fixing	Each.	3
Constructing a laterine	Lump sum Rupees.	
Digging well	Do	
Date stone	Each.	
Levelling compound	Lump sum Rupees.	

A. S. NAGAVKAR, *Executive Engineer.*

MYSORE STATE LIFE INSURANCE.

Circular No. 22, dated 13th March 1895.

To—The District and Taluk Treasury Officers.

Notwithstanding repeated instructions from this office, Treasury officers do not seem to have discontinued the irregular practice of delivering policies after the prescribed time of one month from the date of their receipt at Treasuries. The following Resolution of the Committee passed in the meeting held on the 2nd instant is published below for strict observance in future :—

"The Rule 21 of the State Life Insurance shall be strictly enforced, except when holidays *unexpectedly* granted by Government happen to fall at the close of the prescribed period, in which case the premium must be paid on the first working day when the Treasury re-opens after the holidays."

E. R. SUBRAYER, *Secy. to the Insurance Committee.*